C615/615 Framing #4055



EarthFax
Engineering, Inc.
Engineers/Scientists
7324 So. Union Park Ave.
Suite 100

Midvale, Utah 84047

Telephone 801-561-1555

Fax 801-561-1861

www.earthfax.com

March 22, 2012

Steve Christensen
Permit Supervisor
Utah Division of Oil, Gas and Mining
Coal Program
1594 West North Temple, Suite 1210
P.O. Box 145801
Salt Lake City, UT 84114-5801

Subject: Emery Mine Permit

Groundwater monitoring plan revision

Additional information

Task ID #3898

Dear Mr. Christensen:

At the request of Consolidation Coal Company, I am pleased to submit three hard copies and two CDs with electronic versions of documents addressing the above matter. This submittal also includes executed C1 and C2 forms.

If you have any questions concerning this submittal, please contact John Gefferth at 618-625-6850. Thank you for your assistance.

Sincerely,

Richard B. White, P.E.

Ticlar Brilt

President

EarthFax Engineering, Inc.

Enclosure

Cc: John Gefferth

RECEIVED
MAR 2 3 2012

DIV. OF OIL, GAS & MINING

File in:

Confidential

☐ Shelf Expandable

Pate Folder O JONE S

#### APPLICATION FOR COAL PERMIT PROCESSING

Permit Change New Permit Renewal Exploration	Bond Release	Transfer
Permittee: Consolidation Coal Company		
Mine: Emery Mine	Permi	t Number: 015/015
Title: Groundwater Monitor revision		<u> </u>
<b>Description</b> , Include reason for application and timing required to implement:		
Revision to Groundwater monitoring plan additional information	on Task id 3898	3/12
81		J. 12
<b>Instructions:</b> If you answer yes to any of the first eight (gray) questions, the	his application may re	quire Public Notice publication.
Yes ⋈ No  Yes ⋈ No  Yes ⋈ No  Solution 1. Change in the size of the Permit Area? Acres:  Yes ⋈ No  Yes ⋈ No  Does the application include operations outside a previous of the provided in the size of the Permit Area? Acres:  Yes ⋈ No  Yes ⋈ No  Does the application include operations outside a previous of the previous of the provided in the size of the Permit Area? Acres:  I area? Acres:  I be application of the Permit Area? Acres:  I condition of the Permit Area? Acres.  I condition of the Permit Area?  I cond	rder? DO# iously identified Cumbasins other than as cumbasins other than as cumbication? atrol, right-of-entry, or cemetery or 300 feet NOV # 10088	ulative Hydrologic Impact Area? urrently approved? unce or reclamation bond? compliance information? of an occupied dwelling?
Explain:  Yes No 11. Does the application affect the surface landowner or cl Yes No 12. Does the application require or include underground d Yes No 13. Does the application require or include collection and	hange the post mining	land use? ce and timing? (Modification of R2P2)
Yes No 14. Could the application have any effect on wildlife or ve Yes No 15. Does the application require or include soil removal, s Yes No 16. Does the application require or include vegetation more	egetation outside the c torage or placement? nitoring, removal or re	urrent disturbed area? evegetation activities?
Yes No 17. Does the application require or include construction, n  Yes No 18. Does the application require or include water monitori  Yes No 19. Does the application require or include certified design  Yes No 20. Does the application require or include subsidence con  Yes No 21. Have reclamation costs for bonding been provided?	ng, sediment or drainants, maps or calculation atrol or monitoring?	age control measures? n?
Yes No 22. Does the application involve a perennial stream, a stream Yes No 23. Does the application affect permits issued by other age	encies or permits issue	ed to other entities?
Please attach four (4) review copies of the application. If the mine is on (5) copies, thank you. (These numbers include a copy for the Price Field Office)	or adjacent to Fores	st Service land please submit five
I hereby certify that I am a responsible official of the applicant and that the information contains and belief in all respects with the laws of Utah in reference to commitments, undertakings, and Print Name  NARK T. STANLEY  Print Name	ned/In this application is tru Moligations, herein A Mane, Position, Date	e and correct to the best of my information
Subscribed and sworn to before me this /6th day of MARCH, 20/2	NOTARIAL JANICE L	
Notary Public  Notary Public  My commission Expires:  Attest: State of   County of   Allegheny  October 19, 2013  Ss:	Notary P CECIL TWP., WASHI My Commission Exp	Public NGTON COUNTY
For Office Use Only:	Assigned Tracking Number:	Received by Oil, Gas & Mining
		RECEIVED
		MAR 2 3 2012
		DIV. OF OIL, GAS & MINING

# APPLICATION FOR COAL PERMIT PROCESSING Detailed Schedule Of Changes to the Mining And Reclamation Plan

Permit		ation Coal Co	ompany	
Mine:	Emery Mine			t Number: 015/015
Title:	Revision to gr	oundwater m	onitoring plan, additional information, Task ID #389	98 3/12
applicat of conte	ion. Individually ents, section of the	list all maps a plan, or other	to the Mining and Reclamation Plan, which is required as and drawings that are added, replaced, or removed from the information as needed to specifically locate, identify and and drawing number as part of the description.	e plan. Include changes to the table
			DESCRIPTION OF MAP, TEXT, OR MATERIA	AL TO BE CHANGED
Add		Remove	Chapter VI, page VI-27	
Add		Remove	Chapter VI, page VI-39	
Add		Remove	Chapter VI, page VI-41	
Add		Remove	Chapter VI, Table VI-17	
⊠ Add	Replace	Remove	Chapter VI, One-page letter dated March 12, 2012 - to t	he back of Appendix VI-17
⊠ Add	Replace	Remove	Chapter VI, Appendix VI-17	
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		_
Any oth Aining	er specific or spe and Reclamation	ecial instruction Plan.	on required for insertion of this proposal into the	Received by Oil, Gas & Mining  RECEIVED  MAR 2 3 2012  DIV. OF OIL, GAS & MINING

- 2. Ephemeral streamflow typically carries a high sediment load. This sediment will fill remaining cracks. As the cracks heal, the potential for interception of streamflow is minimized.
- 3. The depressions created by subsidence are sufficiently broad that changes in slope are not typically of an ample magnitude to cause ponding in anything other than local areas.

Potential Hydrocarbon Contamination. Diesel fuel, oils, greases, and other hydrocarbon products are stored and used at the site for a variety of purposes. Diesel and oil stored in aboveground tanks at the mine surface facilities may spill onto the ground during filling of the storage tank, leakage of the storage tank, or filling of the vehicle tank. Similarly, greases and other oils may be spilled during use in surface and underground operations.

The probable future extent of the contamination caused by diesel and oil spillage is expected to be small for three reasons. First, because the tanks are located above ground, leakage from the tanks can be readily detected and repaired. Second, spillage during filling of the storage or vehicle tanks is minimized to avoid loss of an economically valuable product. Finally, the mine has a Spill Prevention Control and Countermeasure Plan that provides inspection, training, and operation measures to minimize the extent of contamination resulting from the use of hydrocarbons at the site.

Motor oil was introduced into some of the monitoring wells several years ago for reasons that are not clear. An investigation of this issue, conducted in January 2012, concluded that this oil is not causing substantial contamination of the monitored aquifers (see Appendix VI-18).

Coal Spillage During Hauling. Coal is hauled over County roads from the mine to State Highway 10 and future destinations. Past experience has indicated that no substantial quantities of coal have been spilled during transport. If coal is spilled, it may wash into local streams during a runoff event prior to cleanup. Possible impacts to the surface water include increases in total suspended solids and turbidity from the fine coal particulates. The probability of a spill occurring in an area sufficiently close to a stream channel to introduce coal to the stream bed is extremely small.

Areal Extent of Probable Hydrologic Consequences. The above discussion indicates that the probable hydrologic consequences of mining at the Emery Mine will be limited in areal extent as follows:

- Contamination from acid- and toxic-forming materials Very limited areal extent of impact, if any.
- Increased sediment yield from disturbed areas No impacts downstream from disturbed
- Impacts to groundwater availability Drawdown of the groundwater potentiometric surface due to mine dewatering may extend northward to an area south of the Emery Town wells, westward to the Joe's Valley-Paradise Fault Zone, eastward to the area of Muddy Creek, and southward to an area north of Ivie Creek.
- Impacts to surface water availability Increased flow in Quitchupah Creek and immediate downstream portions of Ivie Creek.
- Increased total dissolved solids concentrations in surface and groundwater Slight increase in TDS concentrations in Quitchupah Creek and immediate downstream portions of Ivie Creek. Temporary increase in TDS concentrations in the upper Ferron Sandstone adjacent to the mine.
- Flooding and streamflow alteration Very limited areal extent of impact, if any Potential hydrocarbon contamination Very limited areal extent of impact, if any
- MAR 2 3 2012
- Coal spillage during hauling Very limited areal extent of impact, if any.

Revised 03/12

channeled to sedimentation ponds. All surface drainage from the areas above the sites is diverted around the disposal areas using diversion ditches. No permanent impoundments will exist on the completed refuse piles.

#### VI.4.6.3 Impounding Structures

There are no impounding structures within the permit area that are constructed of coal mine waste or are used to impound coal mine waste.

#### VI.4.6.4 Return of Coal Processing Waste to Underground Workings

Coal processing waste is not returned to abandoned underground workings at this mine.

#### VI.4.7 Disposal of Noncoal Mine Waste

Disposal of noncoal mine waste is discussed in Chapter II.

#### VI.4.8 Casing and Sealing of Wells

Each monitoring well or other borehole associated with the Emery Mine has been cased, sealed, or otherwise managed, as approved by the Division, to prevent acid or other toxic drainage from entering ground or surface water, to minimize disturbance to the hydrologic balance, and to ensure the safety of people, livestock, fish and wildlife, and machinery in the permit and adjacent area. The drill logs and completion diagrams for the water wells are contained in Appendix VI-2.

If a water well is exposed by coal mining and reclamation operations, it will be permanently closed unless otherwise managed in a manner approved by the Division (see Section VI.6.5).

#### VI.5 PERFORMANCE STANDARDS

All mining and reclamation operations will be conducted to minimize disturbance to the hydrologic balance within the permit and adjacent areas, to prevent material damage to the hydrologic balance outside the permit area, and support approved post-mining land uses.

#### VI.5.1 Water Quality Standards and Effluent Limitations

Discharges of water from disturbed areas will be in compliance with all Utah and Federal water quality laws and regulations and with effluent limitations for coal mining contained in 40 CFR Part 434.

#### VI.5.2 Sediment Control Measures

All sediment control measures will be located, maintained, constructed and reclaimed according to plans and designs presented in Sections VI.3.2, VI.4.2, and VI.6.

#### VI.5.2.1 Siltation Structures and Diversions

Siltation structures and diversions will be located, maintained, constructed and reclaimed according to plans and designs presented in Sections VI.3.2, VI.4.2, and VI.6.3.

#### VI.6.2.1 Restoring the Natural Drainage Patterns

All natural drainage patterns will be restored during reclamation.

#### VI.6.2.2 Reshaping Cut and Fill Slopes

All cut and fill slopes will be reshaped to be compatible with the post-mining land use and to complement the drainage pattern of the surrounding terrain.

#### VI.6.3 Siltation Structures

#### VI.6.3.1 Maintenance of Siltation Structures

All siltation structures will be maintained until removed in accordance with the approved reclamation plan.

#### VI.6.3.2 Removal of Siltation Structures

When a siltation structure is removed, the land on which the siltation structure was located will be regraded and revegetated in accordance with the reclamation plan presented in Chapter III.

#### VI.6.4 Structure Removal

A timetable for the removal of each structure is presented in Section III.A.2 of this MRP.

#### VI.6.5 Permanent Casing and Sealing of Wells

When no longer needed for monitoring or other use approved by the Division upon a finding of no adverse environmental or health and safety effects, or unless approved for transfer as a water well, each monitoring well or borehole associated with the Emery Mine will be capped, sealed, backfilled, or otherwise properly managed, as required by the Division and in accordance with the most current regulations concerning well abandonment as promulgated by the Utah Division of Water Rights. Permanent closure measures will be designed to prevent access to the mine workings by people, livestock, fish and wildlife, machinery and to keep acid or other toxic drainage from entering ground or surface waters.

Emery Mine Hydrologic Monitoring Program

**TABLE VI-17** 

Parameter	Surface Water Monitoring Stations	Sampled Wells	Other Wells	Springs/Seeps	UPDES Outfalls
Monitoring Site Names	SWMS-1A, SWMS-2, SWMS-3, SWMS-4, SWMS-5, SWMS-8, SWMS-9, SWMS-10	Bryant, Emery Town <sup>(a)</sup> , <del>12, Lewis,</del> Kemmerer, <del>RDA-1,</del> RDA-2, <del>RDA-3,</del> RDA-4, <del>RDA-5,</del> RDA-6, <u>SM1-2, SM1-3, SM1-4, T1, TP, USGS1-2,</u> USGS3-1, USGS4-1	AA, EMRIA #1, EMRIA #2, FC346WW, H-U, I, MUDDY #1, MUDDY #2, MUDDY #4, R-1, R-2, SM1-1, T2, WW1	SP-10, SP-11, SP-13, SP-14, SP-15	001, 002, 003, 004, 005, 006, 007, 009
Monitoring Frequency	Quarterly	Quarterly, except RDA wells (annual)	Quarterly	Quarterly flows. Samples in 2 <sup>nd</sup> and 3 <sup>rd</sup> quarters	Per permit
		Field Measuremen	nts	una o quanters	
Flow	X			X	Х
Water Level		X	X		
pH (field)	X	X		X	X
Sp. Cond. (field)	X	X		X	
Water Temp. (field)	X	X		X	
	4	Laboratory Measurem	nents		
Total Settleable Solids	X				
Total Suspended Solids	X				Х
Total Dissolved Solids	X	X		X	Х
Total Hardness (as CaCO <sub>3</sub> )	X	X		X	
Oil and Grease	X				X
Acidity (as CaCO <sub>3</sub> )	X				
Carbonate	X	X		Х	
Bicarbonate	Χ	X		X	
Alkalinity (as CaCO <sub>3</sub> )					
Calcium, Total	X				
Calcium, Dissolved	Χ	Χ		X	
Chloride	Χ	Χ		X	
Iron, Total	X				Х
Iron, Dissolved		X		X	
Magnesium, Total	X				
Magnesium, Dissolved		Χ		X	
Manganese, Total	X				
Manganese, Dissolved		X		X	
Potassium, Total	X				
Potassium, Dissolved		Χ		X	
Sodium, Total	X				
Sodium, Dissolved		X		X	
Sulfate		X ells (see text), water-quality s		X	

Due to physical limitations in the Emery town wells (see text), water-quality samples will be collected from Well #1 and waterlevel data will be collected from Well #2. Consol will evaluate data collected from the Emery town wells, using hydrographs and other appropriate means, and submit a report of findings to DOGM on a semiannual basis with the annual report.



March 12, 2012



EarthFax
Engineering, Inc.

Engineers/Scientists
7324 So. Union Park Ave.
Suite100
Midvale, Utah 84047
Telephone 801-561-1555
Fax 801-561-1861
www.earthfax.com

Mr. John Gefferth Director, Coal Permitting Consolidation Coal Company P.O. Box 566 Sesser, IL 62884-0566

Subject: Emery Mine Monitoring Well R2

Dear John:

On August 22, 2011 I issued a letter outlining recommendations for future groundwater monitoring at the Emery Mine. In that letter, I recommended that some of the wells be dropped from further monitoring due to the presence of oil in the wells. The Utah Division of Oil, Gas and Mining then requested that additional investigations be conducted to assess the nature and chemical composition of the oil in the wells.

One of the wells that we investigated was R-2U, located near the west-central portion of the mine-plan area. This well is completed with nominal 1-inch diameter steel casing to a depth of approximately 550 feet. During this investigation, we lowered a ½-inch diameter bailer into the well, which became stuck in the well. Significant effort to retrieve this bailer proved ineffective and it became necessary to leave the bailer in the well. Hence, it is no longer possible to measure water levels in this well.

Given this condition, we recommend that monitoring well R-2U be dropped from the list of hydrologic monitoring locations at the Emery Mine.

Please contact me if you have any questions.

Sincerely,

Til

Richard B. White, P.E.

President

EarthFax Engineering, Inc.

#### **APPENDIX VI-18**

Evaluation of Oil in Emery Mine Monitoring Wells



Mr. John Gefferth Director, Coal Permitting Consolidation Coal Company P.O. Box 566 Sesser, IL 62884-0566

Subject: Evaluation of Oil in Emery Mine Monitoring Wells

EarthFax
Engineering, Inc.

Engineers/Scientists
7324 So. Union Park Ave.
Suite 100
Midvale, Utah 84047
Telephone 801-561-1555
Fax 801-561-1861
www.earthfax.com

#### Dear John:

Pursuant to your request, we have conducted an evaluation of oil in selected monitoring wells at the Emery Mine. The purpose of this evaluation was to address comments from the Utah Division of Oil, Gas and Mining regarding the extent and magnitude of potential hydrocarbon contamination of aquifers at the Emery Mine.

Attachment A presents historic water-level data collected from monitoring wells at the Emery Mine. This table indicates that some of the wells experienced probe-access problems beginning in 2001. With a few of the wells experiencing repeated problems, the decision was made by Mine personnel to pour motor oil into these wells in an attempt to allow easier movement of the probe down the well casing. Unfortunately, this made the collection of future water-level data in those wells difficult since oil would coat the probe and not allow a conductive connection to be made with the water surface. Furthermore, due to cross contamination, it appears that a small amount of oil was introduced into a few of the other wells within the Mine's hydrologic monitoring network. As a result, the monitoring data base indicates that the following groundwater monitoring wells at the Emery Mine (see Figure 1) have occasionally been reported as having oil on the water surface:

- AA-U, AA-M
- H-U, H-M, H-L
- I-B, I-M, I-L
- R2-U
- Lewis

In some cases, the record indicates that oil was present on several occasions. In other cases, the record is sporadic in its indication of oil being present. Except for the Lewis well, each of the above wells is completed with nominal 1-inch diameter galvanized steel casing. The Lewis well is a former private water-supply well that has been abandoned.

To verify the presence or absence of oil in the above wells, we conducted the following investigation:

• Lowered an electronic water-level indicator probe into each well to determine if a water-level measurement could be collected. Upon retrieval, the probe was examined to determine if any oil had collected on the probe or the attached measuring tape.

- Lowered a 1/2-inch diameter polyethylene, disposable, weighted bailer into each well to a depth that intersected the water level. Retrieved the bailer from the well and observed the bailer for indications of the presence of oil (i.e., odor, presence of free oil in the bailer, oil on the surface of the bailer, etc.).
- Sampled the liquids in the bailer. If free oil was present in the bailer, a separate sample of this material was collected. Water samples were analyzed by American West Analytical Laboratories in Salt Lake City, Utah for benzene, ethylbenzene, naphthalene, toulene, and total xylenes. Oil samples were analyzed by Savant, Inc. in Midland, Michigan for kinematic viscosity, simulated distillation by gas chromatography, and elemental analysis by ICP.

General observations made during the field investigation are summarized in Table 1. As indicated, three wells (AA-M, H-M, and H-L) contain noticeable quantities of oil on the water surface, although the exact thickness of oil was difficult to measure because of the small diameter of the wells. Well R2-U may have also contained a noticeable quantity of oil, but the bailer used to sample the oil became stuck in the well during this investigation, making quantification impossible.

The results of laboratory analyses of samples collected during this investigation are summarized in Tables 2 and 3, with analytical reports provided in Attachment B. As indicated in Table 2, no constituents were measured in the groundwater at concentrations that exceeded applicable drinking-water standards. Hence, contamination of groundwater due to the presence of oil in the wells is not considered to be problematic. The results presented in Table 3 indicate that the properties of the oil are consistent with motor oil. Thus, it is apparent that this oil did not originate from a spill, a leak, or other mine operations but rather was new motor oil poured into the wells as indicated by Mine personnel.

It appears that the oil in the wells is not causing contamination of the aquifer and presents only logistical problems for the hydrologic monitoring program. Given this condition, I do not consider it necessary to take any immediate action concerning these wells, but recommend that they be abandoned at some future date in accordance with the requirements of the Utah Division of Water Rights that are then in force.

Please contact me if you have any questions.

Sincerely,

Rich

Richard B. White, P.E.

President

EarthFax Engineering, Inc.

TABLE 1

Status of Oil in Emery Mine
Groundwater Monitoring Wells<sup>(a)</sup>

Well	Status	Result
AA-U	Depth to water = 111 ft. No visible oil on the probe. Water sample collected for laboratory analyses. No visible oil in the bailer.	No oil in this well.
AA-M	Depth to water = 97 ft. Probe and bottom of tape was coated with oil. Oil on the tape may be due to coating of the well casing rather than oil standing in the well. Looks and smells like motor oil. Collected a sample of the oil.	Unknown quantity of oil in this well.
H-U	Depth to water = 96 ft. No visible oil on the probe. Water sample collected for laboratory analyses. No visible oil in the bailer.	No oil in this well.
Н-М	Depth to water = 439 ft. Probe and bottom 200 ft of tape was coated with oil. Oil on the tape may be due to coating of the well casing rather than oil standing in the well. Looks and smells like motor oil. Bailer could not be lowered to the water surface. Collected a sample of the oil that coated the tape.	Unknown quantity of oil in this well.
H-L	Depth to water = 108 ft. Probe and bailer coated with oil. Looks and smells like motor oil. Oil appears to be about 2 to 3 ft thick.	2 to 3 ft of oil in this well.
I-B	Depth to water = 127 ft. No visible oil on the probe. Water sample collected for laboratory analyses. No visible oil in the bailer.	No oil in this well.
I-M	Depth to water = 427 ft. No visible oil on the probe. Bailer could not be lowered to the water surface.	No oil in this well.
I-L	Depth to water = 16 ft. No visible oil on the probe. Water sample collected for laboratory analyses. No visible oil in the bailer.	No oil in this well.
R2-U	Depth to water = 542 ft. Probe covered with oil. Bailer became stuck in the well during sampling attempt. Unable to determine thickness of oil in the well. Looks and smells like motor oil.	Unknown quantity of oil in this well.
Lewis	This well is sealed at the surface and no longer accessible. Could not verify the presence or absence of oil.	Well could not be evaluated.

<sup>(</sup>a) Based on data collected 24 Jan 2012

John Gefferth March 12, 2012 Page 4

TABLE 2

Results of Water Analyses

				Drinking			
							Water
Analyte	Units	AA-U	H-U	H-L	I-BG	I-L	Std.
Benzene	mg/L	<0.00100	< 0.00100	0.00119	0.00204	< 0.00100	0.005
Ethylbenzene	mg/L	< 0.00200	< 0.00200	< 0.00200	< 0.00200	<0.00200	0.7
Naphthalene	mg/L	< 0.00200	< 0.00200	< 0.00200	< 0.00200	< 0.00200	
Toluene	mg/L	< 0.00200	< 0.00200	< 0.00200	0.00465	< 0.00200	1.0
Xylenes, Total	mg/L	<0.00200	< 0.00200	< 0.00200	<0.00200	<0.00200	10

Note: Detected analytes are bolded.


**TABLE 3**Results of Oil Analyses

			Monitor	ing Well	
Analyte	Units	AA-M	H-U	H-M	H-L
Kinematic Viscosity @ 40°C	cSt	31.89	0.6718	31.29	0.6666
Kinematic Viscosity @ 100°C	cSt	5.318		5.278	
% Volatilized @ 371°C	Percent	11.0		11.0	<b>44</b>


#### Gas chromatogram of AA-M oil sample:

# Boiling Point (°C) 3000 4500 4500 1500

#### Gas chromatogram of H-M oil sample:



Conclusion: The kinematic viscosity of the oil is consistent with SAE 20 oil or degraded SAE 30 oil. The gas chromatograms are relatively smooth and consistent between samples, indicating that only one product was introduced into the wells and that this product was the same between wells. The boiling points are consistent with motor oil. It is therefore concluded that the product in the wells is motor oil.



John Gefferth March 12, 2012

#### ATTACHMENT A

Historic Water-Level Data

SITE		Depth		SITE		Depth	
NAME	DATE	•	COMMENTS	NAME	DATE	feet	COMMENTS
AA-M			Dil in Well	AA-U	9/28/2011	110.5	
AA-M	6/8/2011	No Access C	Dil in well	AA-U	6/8/2011	111	
AA-M	3/28/2011	No Access C	OIL IN WELL	AA-U	3/28/2011	111	
AA-M	11/24/2010			AA-U	11/24/2010	111	
AA-M	7/20/2010		Oil in well	AA-U	7/20/2010	111	
AA-M			Oil in well	AA-U	6/22/2010	111	
AA-M			Oil in Well	AA-U	3/25/2010	11	
AA-M AA-M	12/29/2009 12/15/2009		No Access Dil in well	AA-U AA-U	12/29/2009 12/15/2009	112 112	
AA-M	12/12/2009		Dil in Well	AA-U	6/3/2009	113	
AA-M	9/22/2008		Oil in Well	AA-U	12/12/2008	111	
AA-M	6/24/2008		Oil in Well	AA-U	9/22/2008	11	
AA-M	3/26/2008		Oil in well	AA-U	6/24/2008	111	
AA-M	12/10/2007		Dil in well	AA-U	3/26/2008	110	
AA-M	9/20/2007		Oil in well	AA-U	12/10/2007	111	
AA-M	6/13/2007	97		AA-U	9/20/2007	111	
AA-M	3/20/2007		OIL IN THE WELL	AA-U	6/13/2007	110.5	
AA-M	11/20/2006		Oil in well	AA-U	3/20/2007	110 111	
AA-M AA-M	9/27/2006 6/29/2006		Oil in well Oil in Well	AA-U AA-U	11/20/2006 9/27/2006	91	
AA-M	3/6/2006		Oil in Well.	AA-U	6/29/2006	110.4	
AA-M	11/28/2005	97.1		AA-U	3/6/2006	110.4	
AA-M	7/8/2005	97.3		AA-U	11/28/2005	111	
AA-M	5/23/2005	97.3		AA-U	7/8/2005	108.8	
AA-M	3/31/2005	97.5		AA-U	5/23/2005		Oil in Well
AA-M	12/27/2004		Dil in Well	AA-U	3/31/2005	111	
AA-M	9/23/2004	96.75		AA-U	12/27/2004	111	
AA-M	6/23/2004	89.3		AA-U	9/23/2004	111.1	
AA-M AA-M	3/30/2004 12/19/2003	89.6 86		AA-U AA-U	6/23/2004 3/30/2004	112.1 112.1	
AA-M	9/18/2003	84.75		AA-U	12/19/2003	112.1	
AA-M	6/25/2003	89.5		AA-U	9/18/2003	111.7	
AA-M	3/26/2003	89.5		AA-U	6/25/2003	118	
AA-M	12/21/2002	91.58		AA-U	3/26/2003	111.67	
AA-M	9/28/2002	91		AA-U	12/21/2002	113.92	
AA-M	6/24/2002	90.3		AA-U	9/28/2002	112.33	
AA-M	3/27/2002	91.2		AA-U	6/24/2002	111.8	
AA-M AA-M	12/17/2001 9/12/2001	No Access 90		AA-U AA-U	3/27/2002 12/17/2001	114.9	
AA-M	6/13/2001	87.8		AA-U	9/12/2001	111.8	
AA-M	3/23/2001	86.2		AA-U	6/13/2001	111.2	
AA-M	3/15/1999	88.5		AA-U	3/23/2001	110.7	
AA-M	12/7/1998	88.8		AA-U	3/15/1999	112.2	
AA-M	9/16/1998	88.5		AA-U	12/7/1998	112.5	
AA-M	6/26/1998	87.800003		AA-U	9/16/1998	112.6	
AA-M	3/24/1998	88.5		AA-U	6/26/1998	112.5	
AA-M	12/18/1997	92.7		AA-U	3/24/1998	113	
AA-M AA-M	9/29/1997 6/20/1997	89.800003 90.2231		AA-U AA-U	12/18/1997 9/29/1997	112.8 111.8	
AA-M	3/21/1997	90.2231		AA-U AA-U	6/20/1997	112.20473	
AA-M	12/5/1996	90.2		AA-U	3/21/1997	111.54856	
AA-M	9/9/1996	89.9		AA-U	12/5/1996	110.8	
AA-M	6/4/1996	88.9		AA-U	9/9/1996	111.5	
AA-M	12/5/1995	90.5		AA-U	6/4/1996	113.9	
AA-M	9/5/1995	92.7		AA-U	12/5/1995	113	
AA-M	6/7/1995	92.5		AA-U	9/5/1995	112.8	
AA-M	3/3/1995	92.8		AA-U	6/7/1995	112.7	
AA-M	12/1/1994	91.3		AA-U	3/3/1995	112.6	
AA-M AA-M	9/9/1994 6/7/1994	92.2 90.3		AA-U AA-U	12/1/1994 9/9/1994	112.3 112.8	
AA-M	3/9/1994	91.1		AA-U	6/7/1994	112.4	
AA-M	12/7/1993	87.2		AA-U	3/9/1994	113	
AA-M	9/8/1993	90		AA-U	12/7/1993	113.1	
AA-M	6/2/1993	87.6		AA-U	9/8/1993	113	
AA-M	3/22/1993	85.3		AA-U	6/2/1993	112.5	
AA-M	3/13/1992	89 -120.4		AA-U AA-U	3/22/1993 3/13/1992	112.6 111.2	
AA-M	6/22/1981						

SITE		Depth		SITE		Depth	
NAME	DATE	feet	COMMENTS	NAME	DATE	feet	COMMENTS
AA-M	5/11/1981	-21.54		AA-Ų	7/23/1981	38.04	
AA-M	4/11/1981	<b>-23</b> .15		AA-U	6/22/1981	-22.91	
AA-M	3/16/1981	-22.92		AA-U	5/11/1981	-123.27	
AA-M	2/9/1981	-21.77		AA-U	4/11/1981	-127.19	
AA-M	1/8/1981	-21.07		AA-U	3/16/1981	-135.73	
AA-M	12/9/1980	-21.77		AA-U	2/9/1981	-136.39	
AA-M	11/7/1980	<b>-</b> 21.3		AA-U	1/8/1981	-136.63	
AA-M	10/13/1980	-21.77		AA-U	12/9/1980	-135.01	
AA-M	9/17/1980	-22.69		AA-U	11/7/1980	-136.39	
AA-M	8/11/1980	-21.69		AA-U	10/13/1980	-136.86	
AA-M	7/16/1980	-18.22		AA-U	9/16/1980	-136.96	
AA-M	6/11/1980	-18.22		AA-U	8/12/1980	-137.71	
AA-M	5/21/1980	-25.15		AA-U	7/16/1980	-141.17	
AA-M	4/19/1980	-25.15		AA-U	6/11/1980	-141.17	
AA-M	3/17/1980	-22.84		AA-U	5/21/1980	-141.17	
AA-M	11/16/1979	-2.23		AA-U	4/19/1980	-118.1	
				AA-U	3/17/1980	-118.1	

SITE		Depth		SITE		Depth	
NAME	DATE	feet	COMMENTS	NAME	DATE	feet	COMMENTS
H-L		No Access	Oil in Well	H-M		No Access	Oil in Well
H-L		No Access	Oil in well	H-M		No Access	Oil in well
H-L		No Access	OIL IN WELL	H-M		No Access	OIL IN WELL
H-L			OIL IN WELL	H-M	11/24/2010		OIL IIN WELL
	11/24/2010		all in wall				all in some
H-L		No Access	oil in well	H-M		No Access	oil in well
H-L		No Access	Oil in well	H-M		No Access	Oil in well
H-L		No Access	Oil in well	H-M		No Access	Oil in well
H-L	12/29/2009		Oil in well	H-M	12/29/2009		Oil in well
H-L	12/14/2009		Oil in well	H-M	12/14/2009		Oil in well
H-L	12/12/2008		Oil in Well	H-M		No Access	Oil in well
H-L	9/20/2008		Oil in Well	H-M	12/12/2008		Oil in Well
H-L	6/24/2008	0	Oil in well	H-M	9/20/2008	0	Oil in Well
H-L	3/28/2008	0	Oil in well	H-M	6/24/2008	0	Oil in well
H-L	12/11/2007	0	Oil in well	H-M	3/28/2008	0	Oil in well
H-L	9/20/2007	51		H-M	12/11/2007	0	Oil in well
H-L	6/14/2007	0		H-M	9/20/2007	0	Oil in well
H-L	3/20/2007	0		H-M	6/14/2007	0	
H-L	11/27/2006	0		H-M	3/20/2007	0	OIL IN THE WELL
H-L	9/27/2006	0	Oil in well	H-M	11/27/2006		Oil in well
H-L	6/29/2006		Oil in Well	H-M	9/27/2006		Oil in well
H-L	3/9/2006		Oil in Well.	H-M	6/29/2006	321	
 H-L	11/22/2005		Oil in well	H-M	3/9/2006		Oil in Well.
<u>-</u> Н-L	7/11/2005		Oil in Well	H-M	11/22/2005		Oil in well could not get a re
H-L	5/23/2005		Oil in Well	H-M	7/11/2005		Oil in Well will not read dept
H-L	3/25/2005	-	Oil in Well	H-M	5/23/2005		Oil in Well
H-L	12/28/2004		Oil in well depth unknown	H-M		-	Oil in Well
		Diy wells	Oil iii well deptil unknown		3/25/2005		
H-L	9/25/2004			H-M	12/28/2004	•	Oil in well depth unknown
H-L	6/18/2004	80.3		H-M	9/25/2004	0	
H-L	3/30/2004	84.3		H-M	6/18/2004	416	
H-L	12/19/2003	19.7		H-M	3/30/2004	414.8	
H-L	9/17/2003	0	Too Oily Probe Wont Read	H-M	12/19/2003	415	
H-L	5/28/2003	89		H-M	9/17/2003		Oily
H-L	3/14/2003	79.17		H-M	5/28/2003	409	
H-L	12/21/2002	84.33		H-M	3/14/2003	417	
H-L	9/23/2002	83.75		н-м	12/21/2002	414.83	
H-L	6/27/2002	83.9		H-M	9/23/2002	412.2	
H-L	3/21/2002	82		н-м	6/27/2002	412.3	
H-L	12/12/2001	84.3		H-M	3/21/2002	409.9	
H-L	9/12/2001	84.2		H-M	12/12/2001	415.1	
H-L	6/13/2001	83.8		H-M	9/12/2001	414.8	
H-L	3/22/2001	80.8		H-M	6/13/2001	412.7	
H-L	3/15/1999	82.8		H-M	3/22/2001	404	
H-L	12/10/1998	84		H-M	3/15/1999	413.2	
H-L	9/16/1998	83.4		H-M	12/10/1998	416.5	
H-L	6/26/1998	83.9		H-M	9/16/1998	417	
H-L	3/31/1998	82.9		H-M	6/26/1998	413.5	
H-L	12/16/1997	83.5		H-M	3/31/1998	413.7	
H-L	9/29/1997	84.200003		H-M	12/16/1997	414.2	
	6/20/1997	84.317588		H-M	9/29/1997	409.90001	
H-L	5/211/19QU/						

SITE		Depth		SITE		Depth	
NAME	DATE	feet	COMMENTS	NAME	DATE	feet	COMMENTS
H-L	12/27/1996	83.7		H-M	3/6/1997	409.90815	
H-L	9/9/1996	83.4		H-M	12/27/1996	410.4	
H-L	6/10/1996	83.1		H-M	9/9/1996	408.5	
H-L	12/6/1995	84.7		H-M	6/10/1996	412.8	
H-L	9/11/1995	91		H-M	12/6/1995	414.9	
H-L	6/7/1995	81		H-M	9/11/1995	415.2	
H-L	3/2/1995	80.8		H-M	6/7/1995	411.2	
H-L	12/1/1994	81.8		H-M	3/2/1995	406	
H-L	9/9/1994	80.3		H-M	12/1/1994	406.2	
H-L	6/8/1994	81.2		H-M	9/9/1994	405.2	
H-L	3/8/1994	80		H-M	6/8/1994	410.6	
H-L	12/8/1993	77.5		H-M	3/8/1994	405.1	
H-L	9/10/1993	78.5		H-M	12/8/1993	402.1	
H-L	6/2/1993	75.8		H-M	9/10/1993	405.3	
H-L	3/4/1993	75.1		H-M	6/2/1993	399.2	
H-L	3/13/1992	71.5		H-M	3/4/1993	400	
H-L	1/14/1985	19.6		H-M	3/13/1992	392.8	
H-L	6/22/1981	-21.91		H-M	1/14/1985	59.9	
H-L	5/11/1981	-22.14		H-M	6/22/1981	-21.24	
H-L	4/11/1981	-21.91		H-M	5/11/1981	-23.55	
H-L	3/16/1981	-23.87		H-M	4/11/1981	-25.86	
H-L	2/9/1981	-38.26		H-M	3/16/1981	-22.39	
H-L	1/9/1981	-23.27		H-M	2/9/1981	-22.39	
H-L	12/10/1980	-17.5		H-M	1/9/1981	-23.31	
H-L	11/8/1980	-22.11		H-M	12/10/1980	-23.31	
H-L	10/13/1980	-15.42		H-M	11/8/1980	-24.24	
H-L	9/17/1980	-10.27		H-M	10/13/1980	-22.85	
H-L	8/11/1980	-11.43		H-M	9/17/1980	-19.18	
H-L	7/15/1980	-16.04		H-M	8/11/1980	-20.63	
H-L	6/10/1980	-16.04		H-M	7/15/1980	-20.63	
H-L	5/21/1980	-16.04		H-M	6/10/1980	-25.25	
H-L	4/18/1980	-16.04		H-M	5/21/1980	-25.25	
H-L	3/14/1980	-16.04		H-M	4/18/1980	-25.25	
H-L	11/15/1979	-13		H-M	3/14/1980	-25.25	
H-L	10/24/1979	-13.5		H-M	11/15/1979	-25	
				H-M	10/24/1979	-60	

SITE		Depth		SITE		Depth	
NAME	DATE	feet	COMMENTS	NAME	DATE	feet	COMMENTS
H-U	9/27/2011	90.5		I-B	9/27/2011	No Access	Oil in Well
H-U	6/21/2011	90.8		I-B	6/8/2011	No Access	Oil in well
H-U	3/29/2011	88		I-B	3/29/2011	No Access	OIL IN WELL
H-U	11/24/2010	85		I-B	10/15/2010	No Access	
H-U	7/21/2010	80		I-B	7/20/2010	No Access	oil in well
H-U	6/23/2010	80		I-B	6/22/2010	No Access	Oil in well
H-U	3/25/2010	80		I-B	3/24/2010	No Access	Oil in well
H-U	12/29/2009	70		I-B	12/29/2009	No Access	Oil in well
H-U	12/14/2009	69		I-B	12/14/2009	No Access	Oil in well
H-U	6/3/2009	69		I-B	6/3/2009	No Access	Oil in well
H-U	12/12/2008	65		I-B	12/12/2008	0	Oil in Well
H-U	9/20/2008	54		I-B	9/20/2008	0	Oil in Well
H-U	6/24/2008	60	hit oil	I-B	6/24/2008	0	Oil in well
H-U	3/28/2008	56		I-B	3/28/2008	0	Oil in well
H-U	12/10/2007	53		I-B	12/10/2007	No Access	Oil in well
H-U	9/20/2007	51		I-B	9/20/2007	0	Oil in well
H-U	6/14/2007	47		I-B	6/14/2007	0	
H-U	3/20/2007	43.5		I-B	3/20/2007	0	OIL IN WELL
H-U	11/27/2006	39		I-B	11/27/2006	0	Oil in well couldn't sample
H-U	9/27/2006	38.5		I-B	9/27/2006	0	Oil in well
H-U	6/29/2006	36		I-B	6/29/2006	68.8	Oil in well
H-U	3/9/2006	34.8		I-B	3/9/2006	70	
H-U	11/22/2005	32.4		I-B	11/17/2005	69.9	
H-U	7/11/2005	32.5		I-B	7/20/2005	69.3	
H-U	5/23/2005	59.7		I-B	5/23/2005	Dry Wells	Probe stops at 66 feet
H-U	3/25/2005	41.4		I-B	3/25/2005	Dry Wells	Probe Stops at 66'
H-U	12/28/2004	53.5		1-B	12/28/2004	Dry Wells	Broken pump down
H-U	9/25/2004	61.75		I-B	9/25/2004	66	no water to sample
H-U	6/18/2004	60.6		I-B	6/18/2004	66	probe catches at 66 feet
H-U	3/30/2004	59.5		I-B	3/18/2004	67	
H-U	12/19/2003	62.5		I-B	12/19/2003	66	probe stops at this depth

SITE		Depth		SITE		Depth	
NAME		eet	COMMENTS	NAME	DATE	feet	COMMENTS
H-U	9/17/2003		Oily	I-B	9/17/2003		Probe stops at 66'
1-U	5/28/2003	56.6		I-B		No Access	Probe stops a 66'
I-U	3/14/2003	58.25		I-B	3/14/2003	66	Probe stops
i-U	12/21/2002	59.08		I-B	12/21/2002		Probes Stops
1-U	9/23/2002	57.7		I-B	9/23/2002	66	
I-U	6/27/2002	57.7		I-B	6/27/2002		probe stops
I-U	3/21/2002	57.3		I-B	3/21/2002		probe stops
I-U	12/12/2001	58.2		I-B	12/12/2001		probe sticks at this depth
I-U	9/12/2001	57.8		I-B	9/12/2001	66	probe sticks at this depth
				I-B	6/13/2001		probe sticks - can't get in any
I-U I-U	6/13/2001	57.1		I-B	3/22/2001	66	probe sticks - can t get in any
	3/22/2001	56.3				66	
I-U	3/15/1999	57.4		I-B	3/17/1999		
-U	12/10/1998	57.5		I-B	12/10/1998	66	
-U	9/16/1998	57.6		I-B	9/8/1998	68	
-U	6/26/1998	57.8		I-B	6/26/1998	68	
-Ų	3/31/1998	57.2		I-B	3/31/1998	68	
I-U	12/16/1997	58.6		I-B	12/12/1997	65.2	
I-U	9/29/1997	56.800002		I-B	9/29/1997		
I-U	6/20/1997	56.758532		I-B	6/20/1997		
-U	3/6/1997	57.906826		I-B	3/6/1997	64.99344	
I-U	12/27/1996	57.5		I-B	12/27/1996	63.5	
I-U	9/9/1996	57.5		I-B	9/9/1996	64.4	
I-U	6/10/1996	57.8		I-B	6/10/1996	61.4	
I-U	12/6/1995	57.9		I-B	12/6/1995	62.7	
I-U	9/11/1995	56.2		I-B	9/11/1995	62.5	
I-U	6/7/1995	57.1		I-B	6/7/1995		
I-U	3/2/1995	56.1		I-B	3/2/1995	61.4	
i-Ü	12/1/1994	57.3		I-B	12/1/1994	60.3	
. U I-U	9/8/1994	57.7		I-B	9/8/1994	60.2	
I-U	6/8/1994	57.7		I-B	6/7/1994	53.8	
1-U	3/8/1994	57.2		I-B	3/8/1994	56.2	
1-U		56.2		I-B	12/8/1993	56.4	
	12/8/1993	50.2		I-B	9/9/1993		
I-U	9/10/1993					56	
I-U	6/2/1993	57.2		I-B	6/2/1993	55	
I-U	3/4/1993	56		I-B	3/3/1993		
I-U	3/13/1992	57		I-B	3/13/1992		
I-U	1/14/1985	57.9		I-B	6/22/1981	10.46	
I-U	6/22/1981	53.53		I-B	5/11/1981	10.25	
I-U	5/11/1981	52.65		I-B	4/11/1981	10.02	
I-U	4/11/1981	52.1		I-B	3/16/1981	9.93	
I-U	3/16/1981	55.8		I-B	2/9/1981	9.31	
I-U	2/9/1981	56.67		I-B	1/9/1981	9.75	
1-U	1/9/1981	56.96		I-B	11/8/1980	9.51	
I-U	11/8/1980	60.99		I-B	10/13/1980	9.78	
-U	10/13/1980	60.75		I-B	9/17/1980	10.14	
-U	9/16/1980	59.74		I-B	8/11/1980	10.58	
-U	8/11/1980	60.45		I-B	7/15/1980	11.01	
I-U	7/15/1980	60.2		1-B	6/10/1980	10.9	
. U I-U	6/10/1980	57.63		I-B	5/21/1980	11.04	
i-U	5/21/1980	56.82		I-B	4/18/1980	11.05	
I-U	4/18/1980	53.68		I-B	3/14/1980	10.47	
1-U	3/14/1980	51.59		I-B	11/15/1979	11.69	
1-U	11/15/1979	64.18		I-B	10/25/1979	9.56	

SITE		Depth		SITE		Depth	
NAME	DATE	feet	COMMENTS	NAME	DATE	feet	COMMENTS
I-L	9/27/2011	18.5		I-M	9/27/2011	No Access	Oil in Well
1-L	6/8/2011	18		I-M	6/8/2011	No Access	Oil in well
I-L	3/29/2011	18		I-M	3/29/2011	No Access	OIL IN WELL
I-L	10/15/2010	18		I-M	10/5/2010	No Access	
I-L	7/20/2010	18		I-M	7/20/2010	No Access	oil in well
l-L	6/23/2010	18		I-M	6/22/2010	No Access	Oil in well
l-L	3/25/2010	18		I-M	3/24/2010	No Access	Oil in Well
l-L	12/29/2009	18		I-M	12/29/2009	No Access	Oil in well
I-L	12/14/2009	18		1-M	12/14/2009	No Access	Oil in well
l-L	6/3/2009	18		I-M	12/12/2008	0	Oil in Well
l-L	12/12/2008	18		I-M	9/20/2008	0	Oil in Well
l-L	9/22/2008	17		I-M	6/24/2008	395	
l-L	6/24/2008	17	Hit oil	I-M	3/28/2008	394	
I-L	3/28/2008	17	Hit oil	I-M	12/10/2007	394	

SITE		Depth		SITE		Depth	
NAME	DATE	feet	COMMENTS	NAME	DATE	feet	COMMENTS
I-L	12/10/2007 9/20/2007	18		I-M I-M	9/20/2007 6/14/2007	13 396	
I-L I-L	6/14/2007	395 13		I-IVI	3/20/2007	396	
I-L	3/20/2007	17		I-M	11/27/2006	395	
I-L	11/27/2006	17		I-M	9/27/2006	395	
I-L	9/27/2006	17.5		I-M	6/29/2006	393.6	
I-L	6/29/2006	18.3		I-M	3/9/2006	390.9	
I-L	3/9/2006	17.6		I-M	11/22/2005	389	
I-L	11/17/2005	18		I-M I-M	7/20/2005 5/23/2005	237.8 233.8	
I-L I-L	7/20/2005 5/23/2005	18.8 18.3		I-M	3/25/2005	234.6	
I-L	3/25/2005	19.1		I-M	12/28/2004	262	
I-L	12/28/2004	18.6		I-M	9/25/2004	262.9	
I-L	9/26/2004	19		I-M	6/18/2004	240.2	
I-L	6/18/2004	18.5		I-M	3/30/2004	249.3	
I-L	3/18/2004	21		I-M	12/19/2003	262	
I-L I-L	12/19/2003 9/17/2003	21.2 19.7		I-M I-M	9/17/2003 5/28/2003	263 242.4	
I-L	5/28/2003	20		I-M	3/14/2003	240.5	
I-L	3/14/2003	16		1-M	12/21/2002	239.33	
I-L	12/21/2002	16		l-M	9/23/2002	238.8	
I-L	9/23/2002	16.75		I-M	6/27/2002	238	
I-L	6/27/2002	17.8		I-M	3/21/2002	238.1	
I-L	3/21/2002	18		I-M	12/12/2001	238.8	
I-L I-L	12/12/2001 9/12/2001	15.8 15.5		I-M I-M	9/12/2001 6/13/2001	238.9 237.6	
1-L 1-L	6/13/2001	15.3		I-M	3/22/2001	237.3	
I-L	3/22/2001	17.9		I-M	3/17/1999	238.2	
I-L	3/17/1999	15.1		I-M	12/10/1998	237.7	
I-L	12/10/1998	15		I-M	9/8/1998	238.2	
I-L	9/8/1998	14		I-M	6/26/1998	239.5	
I-L	6/26/1998	15.1		I-M	3/31/1998	237.8 239.2	
I-L I-L	3/31/1998 12/12/1997	14 14.2		I-M I-M	12/12/1997 9/29/1997	240.00001	
1-L	9/29/1997	15.4		I-M	6/20/1997	239.50132	
I-L	6/20/1997	15.419948		I-M	3/6/1997	240.48557	
I-L	3/6/1997	15.485565		I-M	12/27/1996	241.2	
I-L	12/27/1996	15.8		I-M	9/9/1996	240.7	
I-L	9/9/1996	15		I-M	6/10/1996	241.3	
I-L I-L	6/10/1996 12/6/1995	15.5 15.8		I-M I-M	12/6/1995 9/11/1995	242.2 242.2	
I-L	9/11/1995	17.1		I-M	6/7/1995	242.3	
I-L	6/7/1995	17.1		I-M	3/2/1995	242.8	
I-L	3/2/1995	17		I-M	12/1/1994	243.8	
I-L	12/1/1994	17.3		I-M	9/8/1994	244.1	
I-L	9/8/1994	16.2		I-M	6/7/1994	243.4	
I-L	6/7/1994	16.8		I-M	3/8/1994	242.7	
I-L I-L	3/8/1994 12/8/1993	16.7 16.1		I-M I-M	12/8/1993 9/9/1993	236.8 237.5	
I-L	9/9/1993	16.5		I-M	6/2/1993	238.4	
I-L	6/2/1993	16.9		I-M	3/3/1993	237.2	
I-L	3/3/1993	16.8		I-M	3/13/1992	233.1	
I-L	3/13/1992	13.4		I-M	6/22/1981	105.9	
I-L	6/22/1981	0.37		I-M	5/11/1981 4/11/1981	109.56 111.78	
I-L I-L	5/11/1981 4/11/1981	-0.11 -0.3		I-M I-M	3/16/1981	111.78	
I-L	3/16/1981	-0.47		I-M	2/9/1981	113.7	
I-L	11/18/1980	-1.35		I-M	1/9/1981	115.36	
I-L	10/13/1980	-1.4		I-M	11/8/1980	80.98	
1-L	8/11/1980	-1.07		I-M	10/13/1980	80.08	
I-L	7/17/1980	-1.4		I-M	9/17/1980	79.57	
I-L I-L	7/16/1980 6/10/1980	-1.4 -1.4		I-M J-M	8/11/1980 7/15/1980	77.9 75.62	
1-L 1-L	5/21/1980	-1.4 -1.4		I-M	6/10/1980	74.06	
I-L	4/18/1980	-1.4		I-M	5/21/1980	72.93	
I-L	3/14/1980	-1.4		I-M	4/18/1980	70.94	
I-L	11/15/1979	-1.33		I-M	3/14/1980	68.18	
I-L	10/30/1979	11.33		I-M	11/15/1979	51.14	
				I-M	10/25/1979	62.25	

SITE		Depth	,	SITE		Depth	
NAME	DATE	feet	COMMENTS	NAME	DATE	feet	COMMENTS
SITE   NAME	DATE	Depth feet	COMMENTS	SITE	DATE	Depth	CONMACNITO
LEWIS-U		No Access	COMMENTS	NAME R2-U	9/27/2011	feet 497	COMMENTS
LEWIS-U		No Access		R2-U	6/21/2011	510.11	
LEWIS-U	3/28/2011	No Access		R2-U	3/25/2011	506.8	
LEWIS-U	11/24/2010	No Access		R2-U	10/15/2010	510	
LEWIS-U		No Access		R2-U	7/19/2010	503	
LEWIS-U		No Access	Oil in well	R2-U	6/23/2010	500	
LEWIS-U LEWIS-U		No Access No Access	No Access No Access	R2-U R2-U	3/25/2010 12/29/2009	505	
LEWIS-U		No Access	No Access	R2-U	12/14/2009	535 532	
LEWIS-U		No Access	No Access	R2-U	6/3/2009	532	•
LEWIS-U	12/12/2008	No Access	No Access	R2-U	12/12/2008	550	
LEWIS-U		No Access	No Access	R2-U	9/20/2008	562	
LEWIS-U		No Access		R2-U	6/24/2008	570	
LEWIS-U		No Access		R2-U	3/26/2008	567	
LEWIS-U LEWIS-U	9/20/2007	No Access	No access	R2-U R2-U	12/10/2007		Dry
LEWIS-U		No Access	NO access	R2-U	9/18/2007 6/14/2007	537 563	
LEWIS-U		No Access		R2-U	3/20/2007	488	
LEWIS-U	11/20/2006		No Access to the hole	R2-U	11/20/2006	488	
LEWIS-U	9/27/2006	0	No access to sample	R2-U	9/28/2006	488	
LEWIS-U		No Access	No Access to sample	R2-U	6/29/2006	•	491.0' deep and dry
LEWIS-U		No Access	No access to sample.	R2-U	3/7/2006		Oil in Well.
LEWIS-U	11/28/2005		No access to the well	R2-U	11/28/2005	550.7	0.11.147.11
LEWIS-U LEWIS-U	7/22/2005 5/23/2005		Well is 276 ft. deep and Dry	R2-U R2-U	7/11/2005 5/23/2005		Oil in Well
LEWIS-U	3/31/2005			R2-U	3/23/2005	•	438 Feet and dry
LEWIS-U	12/27/2004	-	Site was dry	R2-U	12/28/2004	•	Site was dry at 488'
LEWIS-U	9/25/2004	-	Not enough water to sample	R2-U	9/20/2004	-	Site was dry
LEWIS-U	6/18/2004	215	probe hangs up	R2-U	6/23/2004	488	•
LEWIS-U	3/29/2004		probe stops at 215 feet	R2-U	3/18/2004		dry
LEWIS-U	12/19/2003	275	D	R2-U	12/19/2003	488	_
LEWIS-U LEWIS-U	9/17/2003 6/12/2003		Dry	R2-U	9/17/2003		Dry
LEWIS-U	3/13/2003	•	Plugged @ 216' Probe Stops	R2-U R2-U	5/28/2003 3/14/2003	Ury vveiis 487	Well dry at 488'
LEWIS-U	12/21/2002		probe pipe plugged at 215 feet	R2-U	12/21/2002	488	
LEWIS-U	9/24/2002	215	, , , , , , , , , , , , , , , , , , , ,	R2-U	9/28/2002	0	
LEWIS-U	6/24/2002			R2-U	6/27/2002	487	
LEWIS-U	3/27/2002	215	probe stops	R2-U	3/1/2002	487	
LEWIS-U	12/17/2001		probe sticks at this point	R2-U	12/17/2001	487	
LEWIS-U LEWIS-U	9/5/2001 6/5/2001		DIS.METALS FILTERED @ LAB	R2-U R2-U	9/12/2001	487 487	
LEWIS-U	3/23/2001	215	DIS.METALS FILTERED @ LAB	R2-U R2-U	6/13/2001 3/22/2001	487	
LEWIS-U	6/13/2000	2.0		R2-U	3/15/1999	401	
LEWIS-U	3/15/1999			R2-U	12/10/1998		
LEWIS-U	12/10/1998			R2-U	9/15/1998		
LEWIS-U	9/8/1998	281.2		R2-U	6/26/1998		
LEWIS-U	6/2/1998	281.2		R2-U	3/31/1998		
LEWIS-U LEWIS-U	3/24/1998 12/18/1997			R2-U R2-U	12/5/1997		
LEWIS-U	9/8/1997	280.900009		R2-U R2-U	9/30/1997 6/20/1997		
LEWIS-U	6/3/1997	279.855652		R2-U	3/3/1997		
LEWIS-U	3/5/1997	278.805783		R2-U	12/5/1996	Dry Wells	
LEWIS-U	12/5/1996	278.3		R2-U	9/9/1996		
LEWIS-U	9/4/1996	270		R2-U	6/10/1996		
LEWIS-U	6/4/1996	275		R2-U	12/5/1995		
LEWIS-U LEWIS-U	12/5/1995 9/5/1995			R2-U R2-U	9/7/1995		
LEWIS-U	9/5/1995	271		R2-U R2-U	6/1/1995 3/2/1995		
LEWIS-U	6/6/1995			R2-U	12/1/1994		
LEWIS-U	6/6/1995	270.8		R2-U	9/8/1994		
LEWIS-U	3/2/1995	271.1		R2-U	6/7/1994		
LEWIS-U	12/1/1994	271.1		R2-U	3/8/1994		
LEWIS-U	9/7/1994	270.0		R2-U	12/7/1993		da da 407 5 1
LEWIS-U LEWIS-U	9/7/1994 6/6/1994	270.3		R2-U R2-U	9/9/1993		dry to 487 feet
LEWIS-U	6/6/1994	268.8		R2-U R2-U	6/4/1993 3/3/1993		dry to 487 feet dry to 487 feet
LEWIS-U	3/8/1994	268.5		R2-U	3/13/1992		a., to 407 166t
LEWIS-U	12/7/1993	267		R2-U	1/14/1985		
LEWIS-U	9/7/1993			R2-U	6/22/1981	-36.17	

SITE		Depth		SITE		Depth	
NAME	DATE	feet	COMMENTS	NAME	DATE	feet	COMMENTS
LEWIS-U	9/7/1993	264		R2-U	5/11/1981	-43.33	
LEWIS-U	6/7/1993			R2-U	4/11/1981	-53.03	
LEWIS-U	6/2/1993	263.8		R2-U	3/16/1981	-47.49	
LEWIS-U	3/3/1993	264.1		R2-U	2/9/1981	-29.43	
LEWIS-U	9/2/1992			R2-U	1/8/1981	-25.08	
LEWIS-U	5/26/1992			R2-U	12/9/1980	-26.2	
LEWIS-U	3/13/1992			R2-U	11/7/1980	-26.43	
LEWIS-U	9/23/1991			R2-U	10/13/1980	-28.05	
LEWIS-U	6/5/1991			R2-U	9/17/1980	-21.39	
LEWIS-U	9/17/1990	-17		R2-U	8/10/1980	36.93	
LEWIS-U	6/8/1990			R2-U	7/15/1980	-11.14	
LEWIS-U	9/11/1989			R2-U	6/11/1980	-11.14	
LEWIS-U	6/30/1989			R2-U	5/2/1980	-15.76	
LEWIS-U	6/24/1986			R2-U	4/18/1980	-15.76	
LEWIS-U	9/19/1985			R2-U	3/14/1980	-15.76	
LEWIS-U	6/20/1985			R2-U	12/7/1979	-175.33	

#### ATTACHMENT B

Laboratory Analytical Reports



Rich White EarthFax Engineering 7324 So. Union Park Ave., # 100 Midvale, UT 84047

TEL: (801) 561-1555

RE: Emery / Consol

Dear Rich White:

Lab Set ID: 1201352

463 West 3600 South

Salt Lake City, UT 84115

American West Analytical Laboratories received 5 sample(s) on 1/25/2012 for the analyses presented in the following report.

Phone: (801) 263-8686 Toll Free: (888) 263-8686

Fax: (801) 263-8687

e-mail: awal@awal-labs.com

All analyses were performed in accordance to The NELAC Institute protocols unless noted otherwise. American West Analytical Laboratories is accredited by The NELAC Institute in Utah and Texas; and is state accredited in Colorado, Idaho, and Missouri. Accreditation documents are available upon request. If you have any questions or concerns regarding this report please feel free to call.

web: www.awal-labs.com

Kyle F. Gross

Laboratory Director

Jose Rocha QA Officer The abbreviation "Surr" found in organic reports indicates a surrogate compound that is intentionally added by the laboratory to determine sample injection, extraction, and/or purging efficiency. The "Reporting Limit" found on the report is equivalent to the practical quantitation limit (PQL). This is the minimum concentration that can be reported by the method referenced and the sample matrix. The reporting limit must not be confused with any regulatory limit. Analytical results are reported to three significant figures for quality control and calculation purposes.

Thank You,



Approved by:

Laboratory Director or designee



Client:

EarthFax Engineering

**Project:** 

Emery / Consol

Lab Sample ID:

1201352-001A

Client Sample ID: H-V **Collection Date:** 

1/24/2012 1130h

Received Date:

1/25/2012 933h

**Analytical Results** 

Method: SW8260C

Contact: Rich White

VOAs MBTEXN List by GC/MS Method 8260C/5030C

Analyzed: 1/26/2012 051h

Units: mg/L

**Dilution Factor:** 1

463 West 3600 South Salt Lake City, UT 84115

Phone: (801) 263-8686 Toll Free: (888) 263-8686

Fax: (801) 263-8687 e-mail: awal@awal-labs.com

web: www.awal-labs.com

Kyle F. Gross Laboratory Director

> Jose Rocha QA Officer

Compound	CAS Number	Reporting Limit	Analytical Result	Qual
Benzene	71-43-2	0.00100	< 0.00100	
Ethylbenzene	100-41-4	0.00200	< 0.00200	
Naphthalene	91-20-3	0.00200	< 0.00200	
Toluene	108-88-3	0.00200	< 0.00200	
Xylenes, Total	1330-20-7	0.00200	< 0.00200	

Surrogate	CAS	Result	Amount Spiked	% REC	Limits	Qual
Surr: Toluene-d8	2037-26-5	0.0504	0.05000	101	77-129	
Surr: Dibromofluoromethane	1868-53-7	0.0505	0.05000	101	80-124	
Surr: 4-Bromofluorobenzene	460-00-4	0.0503	0.05000	101	80-128	
Surr: 1,2-Dichloroethane-d4	17060-07-0	0.0574	0.05000	115	74-151	



Client:

EarthFax Engineering

Contact: Rich White

Project:

Emery / Consol

Lab Sample ID:

1201352-002A

Client Sample ID: H-L

**Collection Date:** 

1/24/2012 1145h

**Received Date:** 

1/25/2012 933h

Method: SW8260C

**Analytical Results** 

VOAs MBTEXN List by GC/MS Method 8260C/5030C

Analyzed: 1/26/2012 114h

Units: mg/L

Dilution Factor: 1

463 West 3600 South

Salt Lake City, UT 84115

**CAS** Reporting Analytical Compound Number Limit Result Qual 71-43-2 Benzene 0.001000.00119 Ethylbenzene 100-41-4 0.00200 < 0.00200 91-20-3 Naphthalene 0.00200 < 0.00200 Toluene 108-88-3 0.00200 < 0.00200 Xylenes, Total 1330-20-7 0.00200 < 0.00200

Phone: (801) 263-8686 Toll Free: (888) 263-8686

Fax: (801) 263-8687

e-mail: awal@awal-labs.com

web: www.awal-labs.com

Surrogate	CAS	Result	Amount Spiked	% REC	Limits	Qual
Surr: Toluene-d8	2037-26-5	0.0510	0.05000	102	77-129	
Surr: Dibromofluoromethane	1868-53-7	0.0521	0.05000	104	80-124	
Surr: 4-Bromofluorobenzene	460-00-4	0.0520	0.05000	104	80-128	
Surr: 1,2-Dichloroethane-d4	17060-07-0	0.0609	0.05000	122	74-151	

Kyle F. Gross Laboratory Director

> Jose Rocha QA Officer



Client:

EarthFax Engineering

Project:

Emery / Consol

Lab Sample ID:

1201352-003A

Client Sample ID: I-L

**Collection Date:** 

1/24/2012 1210h

Received Date:

1/25/2012 933h

Analytical Results

Method: SW8260C

VOAs MBTEXN List by GC/MS Method 8260C/5030C

Contact: Rich White

Analyzed: 1/26/2012 136h

Units: mg/L

**Dilution Factor:** 1

463 West 3600 South Salt Lake City, UT 84115

Phone: (801) 263-8686 Toll Free: (888) 263-8686

Fax: (801) 263-8687

e-mail: awal@awal-labs.com

web: www.awal-labs.com

Kyle F. Gross Laboratory Director

> Jose Rocha QA Officer

Compound	CA Num	-	Reporting Limit	Analytical Result	Qual
Benzene	71-43	3-2	0.00100	< 0.00100	
Ethylbenzene	100-4	1-4	0.00200	< 0.00200	
Naphthalene	91-20	)-3	0.00200	< 0.00200	
Toluene	108-8	8-3	0.00200	< 0.00200	
Xylenes, Total	1330-2	20-7	0.00200	< 0.00200	

Surrogate	CAS	Result	Amount Spiked	% REC	Limits	Qual
Surr: Toluene-d8	2037-26-5	0.0492	0.05000	98.4	77-129	
Surr: Dibromofluoromethane	1868-53-7	0.0499	0.05000	99.8	80-124	
Surr: 4-Bromofluorobenzene	460-00-4	0.0492	0.05000	98.5	80-128	
Surr: 1,2-Dichloroethane-d4	17060-07-0	0.0575	0.05000	115	74-151	



Client:

EarthFax Engineering

Emery / Consol

Project:

Emery / Consol

Lab Sample ID:

1201352-004A

Client Sample ID: I-BG

υ. I-DO

**Collection Date:** 

1/24/2012 1215h 1/25/2012 933h

Received Date:

Method: SW8260C

Contact: Rich White

**Analytical Results** 

VOAs MBTEXN List by GC/MS Method 8260C/5030C

Reporting

Limit

0.00100

0.00200

0.00200

0.00200

0.00200

Analytical

Result

**0.00204** < 0.00200

< 0.00200

0.00465

< 0.00200

Qual

**Analyzed:** 1/26/2012 159h

Units: mg/L

Compound

Ethylbenzene

Naphthalene

Benzene

Toluene

Dilution Factor: 1

463 West 3600 South

Salt Lake City, UT 84115

Phone: (801) 263-8686 Toll Free: (888) 263-8686

Fax: (801) 263-8687

e-mail: awal@awal-labs.com

web: www.awal-labs.com

.com Xylenes, Total
Surrogate

Surrogate	CAS	Result	Amount Spiked	% REC	Limits	Qual
Surr: Toluene-d8	2037-26-5	0.0501	0.05000	100	77-129	
Surr: Dibromofluoromethane	1868-53-7	0.0503	0.05000	101	80-124	
Surr: 4-Bromofluorobenzene	460-00-4	0.0521	0.05000	104	80-128	
Surr: 1,2-Dichloroethane-d4	17060-07-0	0.0581	0.05000	116	74-151	

CAS

Number

71-43-2

100-41-4

91-20-3

108-88-3

1330-20-7

Kyle F. Gross Laboratory Director

> Jose Rocha QA Officer

> > Report Date: 1/27/2012 Page 5 of 6



Client:

EarthFax Engineering

Project:

Emery / Consol

Lab Sample ID:

1201352-005A

Client Sample ID: AA-V

**Collection Date:** 

1/24/2012 1400h

Received Date:

1/25/2012 933h

Method: SW8260C

Reporting

Analytical

Result

< 0.00100

< 0.00200

< 0.00200

< 0.00200

< 0.00200

Qual

Contact: Rich White

VOAs MBTEXN List by GC/MS Method 8260C/5030C

CAS

**Analytical Results** 

Analyzed: 1/26/2012 221h

Units: mg/L

Dilution Factor: 1

463 West 3600 South Salt Lake City, UT 84115

Compound Number Limit 71-43-2 Benzene 0.00100 Ethylbenzene 100-41-4 0.00200 Naphthalene 91-20-3 0.00200 Toluene 108-88-3 0.00200 Xylenes, Total 1330-20-7 0.00200

Phone: (801) 263-8686 Toll Free: (888) 263-8686

Fax: (801) 263-8687

e-mail: awal@awal-labs.com

web: www.awal-labs.com

Surrogate CAS Result **Amount Spiked** % REC Limits Qual Surr: Toluene-d8 2037-26-5 0.0491 0.05000 98.3 77-129 Surr: Dibromofluoromethane 1868-53-7 0.04850.05000 97.0 80-124 Surr: 4-Bromofluorobenzene 460-00-4 0.0491 0.05000 98.2 80-128 Surr: 1,2-Dichloroethane-d4 17060-07-0 0.0549 0.05000 110 74-151

Kyle F. Gross Laboratory Director

> Jose Rocha QA Officer

> > Report Date: 1/27/2012 Page 6 of 6

# American West Analytical Laboratories

<b>WORK O</b>	WORK ORDER Summary					Work Order:	1201352
Client:	EarthFax Engineering					Page 1 of 1	1/25/2012
Client ID:	EAR100		Contact: Ric	Rich White		)	
Project:	Emery / Consol		QC Level: LEV	LEVEL I		WO Type:	Standard
Comments:	PA Rush;		1450			•	र्
Sample ID	Client Sample ID	Collected Date	Received Date	Date Due	Matrix	Test Code	Sel Storage
1201352-001A	H-V	1/24/2012 1130h	1/25/2012 0933h	2/3/2012	Aqueous	8260-W-PPM	Purge 2
1201352-002A	H-L	1/24/2012 1145h				8260-W-PPM	✓ Purge
1201352-003A	Т	1/24/2012 1210h				8260-W-PPM	✓ Purge
1201352-004A	I-BG	1/24/2012 1215h				8260-W-PPM	Purge
1201352-005A	AA-V	1/24/2012 1400h				8260-W-PPM	Purge

Page Labora i Oklika 463 West 3600 South (888) 263-8686 Salt Lake City, Utah Fax (901) 263-8687 84115 Email:awal@awal-labs.com CHAIN OF CUSTODY AMERICAN ANALYTICAL LABORATORIES Time Time Date Received By: Signature PRIN NAME PRINT NAME -4048 Jain Dark Auc Time State Fax Address 7324 South Phone 801-561-1555 Client Forth Fax Mishela Contact Rie Land Relinquished By: Signature PRINT NAME Project Project Sample PRINT NA Relinquish PRINT NA PRINT NA E-mail Reimquish

Lab Sample Set # \201352

1 day 2 day 3 day 4 day 5 day Standard Turn Around Time (Circle One)

rubite Acartatorica	700				IESIS	ES IS REQUIRED	QC LEVEL	LABORATORY USE ONLY
Name Enery/Conso	0			(leto				SAMPLES WERE:
: Number/P.O.#			i.	<u> </u>			1 2 2+	Notes:
er Name Tim Jimene 2	27		Collected				3 3+ 4	2 Ambient or Chilled
Sample ID			kittsM				C. L.	3 Temperature 5.0
7-1			W 25 11 51/25/1	100			COMMENTS	4 Received Broken/Leaking (Improperly Sealed)
ナト			56:11	=				Notes:
7			12,10					5 Properly Preserved
-136			51,21					Checked at Bench
0-€.			14100	P <sub>X</sub>				Notes:
								6 Received WithIn
								Z X
								<u> </u>
								· T
								Coc Tape Was:
								1 Present on Outer
ned By. Signature	Date VI2	Received By: Signature	: Signature		Date // Specie	Special Instructions:		Y N NA
		PRINTNAME	IME // C	1	Time			2 Unbroken on Outer
7010	71	W/2	12 thyward		733			Package
ned By: Signature	Date	Received By: Signat	r. Signature	<u> </u>	Date			
WE	Time	PRINT NAME	3		Time			3 Present on Sakrpte NA
ted By: Signature	Date	Received By: Signal	: Signature	╠	Date			4 Unbroken on Sample
WE	Time	PRINT NAME	ш		Time			
								Sample Labels and COC
led by: Signature	Date	Received By: Signature	: Signature	2	Date			Record?

Z

Notes:

. 7 7



4800 JAMES SAVAGE ROAD MIDLAND, MICHIGAN 48642 TELEPHONE (989) 496-2301 FACSIMILE (989) 496-3438

http:\\www.savantgroup.com email: savant@savantgroup.com

2012 February 22

Mr. Richard White

EARTHFAX ENGINEFRING
7324 S. Union Park Avenue
Suite 100

Midvale, UT 84047

Ref: EarthFax Engineering Sample ID: H-M, H-L, H-V & AA-M

Savant Sample ID: S120131D through G Savant Lab Code: EEI01-2012-001

Dear Mr. White:

Enclosed are the test results for your sample(s) listed above which were emailed to you on February 15. Please call if you have any questions regarding the data.

We appreciate your business with Savant Laboratory.

Best regards,

Rebecca Cox

Rebecca Cox Vice President, Operations & Finance

sd

Enclosure



## **EarthFax Engineering**

# Kinematic Viscosity ASTM D445

Customer ID:	Savant ID:	@ 40°C (cSt)	@ 100°C (cSt)
H-M	S120131D	31.29	5.278
H-L	S120131E	0.6666	*
H-V	S120131F	0.6718	*
AA-M	S120131G	31.89	5.318

<sup>\*</sup> Unable to obtain viscosity at temperature

Theodore W. Selby

Director, R & D



### **EarthFax Engineering**

# Simulated Distillation by Gas Chromatography ASTM D6417

Customer ID:	Savant ID:	% Volatized @ 371°C
H-M	S120131D	11.0
AA-M	S120131G	11.0

Theodore W. Selby Director, R & D

Sample name : S120131D

Acquired on : 2/8/2012 11:01:51 PM Vial : 8 Processed on : 2/9/2012 9:39:21 AM Injection : 1 Sample type : Sample Sample (g) : 0.1059 Method name : 2887EXTA Solvent (g) : 1.1910 Operator : CPOR ISTD (g) : 0.0000 Sequence name : C:\Chem32\1\DATA\d120208\S120208 2012-02-08 16-29-28\S120208.S

Data File : D120208\S120208 2012-02-08 16-29-28\008F1001.D\

#### General Variables

Used Blank d120208\s120208 2012-02-08 16-29-28\001f0901.d d120124\s120124 2012-01-25 09-22-37\002f0201.d

Used Start elution (min) 0.213 Used End elution (min) 32.747 Total area 1377614

#### **BP** Distribution table - Percent

Recovered mass%	BP °C						
IBP	288.6	26.0	399.0	52.0	429.4	78.0	461.6
1.0	304.0	27.0	400.6	53.0	430.6	79.0	463.0
2.0	322.4	28.0	401.8	54.0	431.8	80.0	464.6
3.0	332.8	29.0	403.2	55.0	432.8	81.0	466.2
4.0	342.0	30.0	404.4	56.0	432.8	82.0	
5.0	342.0	31.0	405.8		435.0		468.0
6.0	353.4	32.0	407.0	57.0		83.0	469.8
				58.0	436.0	84.0	471.6
7.0	357.6	33.0	408.2	59.0	437.0	85.0	473.4
8.0	361.8	34.0	409.6	60.0	438.2	86.0	475.4
9.0	365.2	35.0	410.6	61.0	439.2	87.0	477.6
10.0	368.2	36.0	411.8	62.0	440.6	88.0	479.6
11.0	371.2	37.0	413.2	63.0	441.6	89.0	482.0
12.0	373.8	38.0	414.2	64.0	442.8	90.0	484.4
13.0	376.2	39.0	415.4	65.0	444.2	91.0	487.0
14.0	378.4	40.0	416.6	66.0	445.2	92.0	489.8
15.0	380.6	41.0	417.6	67.0	446.4	93.0	493.0
16.0	382.8	42.0	418.6	68.0	447.6	94.0	496.4
17.0	384.6	43.0	419.8	69.0	448.8	95.0	500.6
18.0	386.4	44.0	421.0	70.0	450.0	96.0	505.6
19.0	388.2	45.0	421.8	71.0	451.4	97.0	512.2
20.0	389.8	46.0	423.0	72.0	453.0	98.0	521.4
21.0	391.6	47.0	424.2	73.0	454.2	99.0	536.8
22.0	393.4	48.0	425.4	74.0	455.6	FBP	550.2
23.0	394.8	49.0	426.4	75.0	456.8		J. J. J. L.
24.0	396.2	50.0	427.4	76.0	458.4		
25.0	397.8	51.0	428.4	77.0	459.8		

1

Sample name

: S120131D

Acquired on Processed on

: 2/8/2012 11:01:51 PM

: 2/9/2012 9:39:21 AM


Vial Injection : 8 : 1 2

Data File

: D120208\S120208 2012-02-08 16-29-28\008F1001.D\

#### BP Distribution table - cut points

BP	Recovered	Fraction
°C	mass%	mass%
371.0	11.0	11.0



Sample name : S120131G

Acquired on : 2/8/2012 11:50:42 PM Vial : 9 Processed on : 2/9/2012 9:39:23 AM Injection : 1 Sample type : Sample Sample (g) : 0.1025 Method name : 2887EXTA Solvent (g) : 1.2379 : CPOR Operator ISTD (g) : 0.0000 : C:\Chem32\1\DATA\d120208\S120208 2012-02-08 16-29-28\S120208.S Sequence name

Data File : D120208\S120208 2012-02-08 16-29-28\009F1101.D\

#### **General Variables**

Used Blank d120208\s120208 2012-02-08 16-29-28\001f0901.d d120124\s120124 2012-01-25 09-22-37\002f0201.d

Used Start elution (min) 0.200 Used End elution (min) 32.573 Total area 1492928

#### **BP** Distribution table - Percent

Recovered	BP	Recovered	BP	Recovered	BP	Recovered	BP
mass%	°C	mass%	°C	mass%	°C	mass%	°C
IBP	286.8	26.0	399.2	52.0	429.8	78.0	461.6
1.0	303.2	27.0	400.6	53.0	431.0	79.0	463.4
2.0	321.2	28.0	402.0	54.0	432.2	80.0	464.8
3.0	332.0	29.0	403.4	55.0	433.0	81.0	466.6
4.0	341.4	30.0	404.8	56.0	434.2	82.0	468.2
5.0	347.6	31.0	406.0	57.0	435.4	83.0	470.0
6.0	353.0	32.0	407.2	58.0	436.4	84.0	471.8
7.0	357.4	33.0	408.6	59.0	437.4	85.0	473.8
8.0	361.6	34.0	409.6	60.0	438.4	86.0	475.6
9.0	365.0	35.0	410.8	61.0	439.6	87.0	478.0
10.0	368.0	36.0	412.2	62.0	440.8	88.0	480.0
11.0	371.0	37.0	413.4	63.0	442.0	89.0	482.2
12.0	373.6	38.0	414.4	64.0	443.2	90.0	484.6
13.0	376.0	39.0	415.6	65.0	444.2	91.0	487.4
14.0	378.4	40.0	416.8	66.0	445.4	92.0	490.2
15.0	380.6	41.0	417.8	67.0	446.8	93.0	493.4
16.0	382.8	42.0	419.0	68.0	447.8	94.0	496.8
17.0	384.6	43.0	420.0	69.0	449.2	95.0	500.8
18.0	386.4	44.0	421.2	70.0	450.4	96.0	505.8
19.0	388.2	45.0	422.2	71.0	451.8	97.0	512.2
20.0	389.8	46.0	423.4	72.0	453.0	98.0	521.4
21.0	391.8	47.0	424.6	73.0	454.4	99.0	536.2
22.0	393.4	48.0	425.6	74.0	455.8	FBP	549.8
23.0	394.8	49.0	426.6	75.0	457.2		
24.0	396.4	50.0	427.8	76.0	458.8		
25.0	397.8	51.0	428.8	77.0	460.2		

1

Sample name

: S120131G

Acquired on

: 2/8/2012 11:50:42 PM

Vial

: 9 : 1

2

Processed on

: 2/9/2012 9:39:23 AM


Injection

Data File

: D120208\S120208 2012-02-08 16-29-28\009F1101.D\

#### BP Distribution table - cut points

BP	Recovered	Fraction
°C	mass%	mass%
371.0	11.0	11.0





# **EarthFax Engineering**

# Elemental Analysis by ICP ASTM D4951 (ppm)

Customer ID:	H-M	AA-M
Savant ID:	S120131D	S120131G
Silver	*	*
Aluminum	6	*
Boron	*	*
Barium	*	*
Calcium	8	18
Chromium	*	*
Copper	*	*
Iron	49	*
Potassium	*	*
Magnesium	5	*
Manganese	*	*
Molybdenum	· *	*
Sodium	*	*
Nickel	*	*
Phosphorus	8	19
Lead	*	6
Antimony	*	*
Silicon	12	*
Tin	*	*
Titanium	*	*
Vanadium	*	*
Zinc	191	98

<sup>\*</sup> Denotes <5

Theodore W. Selby

Director, R & D